

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-193-20014-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
APR 29 1969  
CONSERVATION DIVISION  
Wichita, Kansas

429-69

Operator's Full Name Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas,

Lease Name Garvey Well No. A-1

Location CSE-SW Sec. 7 Twp. 8 Rge. (E) (W) 35

County Thomas Total Depth 4930

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Gabbert-Jones, Incorporated,

Address: 830 Sutton Place, Wichita, Kansas. License No.     

Operation Completed: Hour 2:00PM Day 25 Month 4 Year 1969

The Above well was plugged as follows:

248'--8 5/8" Surface casing, cement circulated with 270 Sx.  
Top of Dakota section @ 1700'.

Circulated hole with heavy mud. Pulled DP to 1920' and displaced 100 Sx. cement thru  
DP from 1920' to 1600'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from  
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. A. Nichols  
Well Plugging Supervisor

DATE 4/29/69

INV. NO. 9672-W