

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 6 1969

CONSERVATION DIVISION
Wichita, Kansas

8-6-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-193-20021-00-00

Operator's Full Name Murfin, Nadel & Gussman,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Dawes Well No. 1

Location CNW-SW Sec. 31 Twp. 8 Rge. (E) (W) 35

County Thomas Total Depth 5050'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 6:00 PM Day 3 Month 8 Year 1969

The above well was plugged as follows:

268'--8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ 1650'.

Circulated hole with heavy mud. Pulled DP to 1875' and displaced 100 Sx. cement thru
DP from 1875' to 1550'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. S. Nichols
Well Plugging Supervisor

DATE 8/6/69
INV. NO. 256-4