

15-163-21182-00-00

FORM CP-2

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

RECEIVED State Corporation Commission
STATE CORPORATION COMMISSION

CONSERVATION DIVISION

(Oil, Gas and Water)

JUN - 1 1982

200 Colorado Derby Building
WICHITA, KANSAS 67202

CONSERVATION DIVISION
Wichita Kansas

VERBAL PERMIT FORM 6/1/82
(To be filed by Plugging Agent)

Dear Sir:

Mr. Millard Kelso of Kelso Casing has this date requested permission to plug the following described well:

Operator's Full Name: Green & Green

Complete Address: Box 503 - Harp, KS 67601

Lease Name: Maignist Well No. 1

Location: NE SE NW Sec. 9 Twp. 9 Rge. 17 (E) (W)

County: Rock Total Depth: 3580

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Kelso was instructed to plug the well as follows:

8 5/8" @ 204' w/175 sx - 5 1/2" @ 3576 w/175 sx
Top perf 3192 - plug @ 3250 - Cast plug @ 3100 w/
100' sand + 55x cmt. - Recovered 2542' of 5 1/2" casing
Ordered 140 sx 50/30 pag. 6% gel 4% cc 20 gel - 5 hulls
F 8 5/8 plug - Pumped in 4 hulls => 15 gel => 1 hull => 10 cmt.
=> 5 gel => R plug => 70 cmt.

Very truly yours,

Dennis Hamel
Conservation Division Agent