

State of Kansas



15-163-20009-00-00

State Corporation Commission

CONSERVATION DIVISION

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1967
3-20-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Thompson of Garvey Drilling has this

date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.,

Complete Address: 300 West Douglas Wichita, Kansas

Lease Name: O'Brien "DU" Well No. 1

Location: NW/4 NE/4 NE/4 Sec. 14 Twp. 9 Rge. 18 (E)(W) X

County Rooks Total Depth 3230 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Thompson was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace
20 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Ray J. Marvick
Conservation Division Agent