

State of Kansas



15-163-20106-00-00

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 2 1968
CONSERVATION DIVISION
Wichita, Kansas
5-2-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Cameran of H - 30 Inc., has this

date requested permission to plug the following described well:

Mr. Cameran guarantees payment of the plugging fee.

Operator's full Name: Three G Oil, Inc.,

Complete Address: 1101 Wichita Plaza Wichita, Ks.

Lease Name: McConchie Well No. 1

Location: SW SW SE Sec. 15 Twp. 9 Rge. 18 (E)(W) X

County Rooks Total Depth 3360' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cameran was instructed to plug the well as follows:

Run pits, circulate heavy mud, set cementing plug at 800' and displace
70 sc cement thru drill pipe, Heavy mud to 180' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug. 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Leo J. Massey
Conservation Division Agent