

State of Kansas



15-163-20168-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 7 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 1-7-69

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Walker of Rains & Williamson has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: R & W, Three G, & Petr. Inc.

Complete Address: 1525 Plaza Bldg., Wichita, Ks.

Lease Name: Havlas Well No. 1

Location: 2200' FNL, 2200' FEL Sec. 15 Twp. 9 Rge. 16 (E)(W) X

County: Rooks Total Depth 3518' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Walker was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace
70 sk cement thru drill pipe. Heavy mud to 210' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Leo F. Messer
 Conservation Division Agent