

15-163-04131-0000

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 28 1962

CONSERVATION DIVISION
Wichita, Kansas

2/28/62

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rooks

Location: SE NE SW Sec. 9 Twp. 9 Rge. _____ (E) _____ (W) 17

Name of Field: _____ Total Depth: 3535

I have this date completed supervision of plugging of:

Lease Name: Fike Well No. 1

Operator's Full Name: Morganstern - Specter

Complete Address: Box 661 Russell, Kansas

Plugging Contractor Knight Casing Pulling

Address: Chase, Kansas License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 4PM Day 22 Month 2 Year 62

The above well was plugged as follows:

8 5/8" 202' circulated with cement - 4 1/2" 3534' with 125 sax cement.

Filled with sand to 3520', set 4 sax cement with dump bailer, pulled

2730' 4 1/2" to 550', circulated hole with heavy mud through 4 1/2" (37 Sax Gel)

displaced 20 sax cement through 4 1/2" at 550', heavy mud to 180', displaced

20 sax cement through 4 1/2" at 180', heavy mud to 35', set bridge and 10 sax

cement to bottom cellar.

Signed: Edon Petty
Conservation Division Agent

Reviewed: Harold Hollis
Field Supervisor

Remarks:

INVOICED

DATE 3/6/62

INV. NO. 4588-W