

15-163-19230-00-00

R

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

5/7/59

MAY 7 1959

CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 32-40 County: Rooks

Location: CE $\frac{1}{2}$  SE SW Sec. 9 Twp. 9 Rge. 17 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3489

I have this date completed supervision of plugging of:

Lease Name: Fike Well No. B-1

Operator's Full Name: Murfin Drg Co

Complete Address: 617 Union Center Wichita, Kans

Plugging Contractor: Ace Pipe Pulling Co

Address: Great Bend, Kans License No. 2

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 3PM Day 28 Month 4 Year 59

The above well was plugged as follows:

8 5/8" at 182'ncirculated with cement - 5 1/2" 3482' with 50 sax cement.

PB to 3450', perf 3412'

Filled with sand to 3400', set 4 sax cement with dump baler, pulled 2205'

5 1/2" to 500', circulated hole with heavy mud at 500' (Gel), displaced

20 sax cement through 5 1/2" at 500', heavy mud to 150', displaced 20 sax

cement through 5 1/2" at 150', heavy mud to 35', setbridge and 10 sax cement

to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: *Edon Petty*  
Conservation Division Agent

Reviewed: *J. Lewis Brock*  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC 9 T 9 R 17  
BOOK PAGE 32 LINE 40