

15-163-03126-00-07

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1963

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Cooperative Refg Assn

Complete Address: Drawer "C" Great Bend, Kansas

Lease Name Hrabe Well No. 1

Location SW SW NE Sec. 12 Twp. 9 Rge. - (E) - (W) 17

County Rooks Total Depth 3423

Abandoned Oil Well x Gas Well - Input Well - SWD Well - D & A -

Other well as hereafter indicated: -

Plugging Contractor: Coop & Halliburton Cementing Co

Address: - License No. -

Operation Completed: Hour 11AM Day 19 Month 9 Year 63

The Above well was plugged as follows:

8 5/8" 156' circulated with cement - 5 1/2" 3399' with 90 sax cement - DV
tool set and circulated to (0) with cement (no pipe recovery) - hole in
pipe at 979' - lost pipe scraper in hole at 1617' - unable to fish out -
run measuring line - weight stopped at 1140'

Run tubing in hole to 1097' - pumped 130 sax gel mixed with 12 sax
celo seal and 10 sax hulls through tubing - pumped 145 sax cement through
tubing, filling hole with cement from 1140' to 0' - hooked pump back on
casing and pressured up to 600' to test cementing job.

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

DATE

9/24/63

INV. NO.

9489-4

Signed:

Well Plugging Supervisor