

15-163-03128-0000

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 95-5

LOCATION NW SE SW

SEC. 12 TWP. 9 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 3 Lease Mc Clay

Operator Co-Op Refg Assn Address Box 765 Great Bend, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3468 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 216' circulated with cement - 5 1/2" at 3462' with 200  
sax cement behind - Baker Plugs 3212' - perforations at  
3207' - Filled with chat to 3165', set 4 sax cement with  
damp bailer, pulled 1800' 5 1/2", filled with mud to 216', set  
rock and 15 sax cement, mud to 35', set rock and 10 sax cement  
to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 6 1953

CONSERVATION DIVISION  
Wichita, Kansas

*[Signature]*  
District Conservation Agent

Date 7-2-53

**PLUGGING**  
FILE SEC 12 T 9 R 17w  
BOOK PAGE 95 LINE 5