

15-163-03131-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW NW NE

SEC. 12 TWP. 9 RGE. 17

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Hrabe

Operator Chas Gabbert Drg Co Address Great Bend, Kans

Field Westhusin County Rooks

Total Depth 3496 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 192' circulated with cement - 5 1/2" at 3496 with 75 sax

behind - Lane-Wells plugs to 3382 - perf. at 3340 and squeezed

with 100 sax, another perf at 3250 and squeezed with 100 sax.

top perf at 3208'. filled hole to 3180 with chat, run 5 sax

cement with dump bailer, pulled 2000' of 5 1/2", mudded hole with

heavy mud to 190', set wood plug, rock bridge and 15 sax cement,

filled with heavy mud to 30', set wood plug, rock bridge and 10

sax cement to bottom cellar.

[Signature]
District Conservation Agent

Date 11-16-49

PLUGGING
FILE SEC 12 T 9 R 17
BOOK PAGE 125 LINE 9

11/18/49

NOV 18 1949
STATE CORPORATION
COMMISSION
KANSAS