

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 13 1976

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 1103 - 04138 - 00 - 01 (of this well)
Wichita, Kansas

Operator's Full Name Atlantic Richfield Company

Complete Address Box 849, Great Bend, Kansas 67530

Lease Name Flora A. McClay Well No. 1

Location NW SW Sec. 12 Twp. 9 Rge. (E) (W) 17

County Rooks Total Depth 3340'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Co. Tools by Halliburton Cementing Co.

Address Hays, Ks. License No. _____

Operation Completed: Hour 4 P Day 11 Month 5 Year 1976

The above well was plugged as follows:

Total Depth 3340' 10 3/4" csg set 109' cwc 125 sx.

7" csg set 3150' cw 125 sx.

5" csg set 3340' cw 25 sk cem. 5 1/2" csg perf. in LKC. (3210-3300) No pipe recovered.

Set tbg. at 1540' -pumped 100 sk cem. & 15 sk gel W/200 lbs hulls.

Pumped 30 sk gel W/500 lbs hulls & circ. to surface.

Displaced 50 sk cem. -Pulled tbg to 600' & disp. 50 sk cem.

Pulled tbg. set solid bridge at 100' & filled to surface W/15 sk cem.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Massey
Well Plugging Supervisor

INVOICED

DATE 5/13/76

INV. NO. 3209-W