

15-163-19235-00-00

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION E W 1/2 SW SE

SEC. 12 TWP. 9 RGE. 17 W

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Smith

Operator Plainstock Oil & Gas Co. Address Plainville, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3420 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

9 5/8 ? - 7" at 3169' - 4" liner from 3167' to 3420'

Filled with sand to 3390', set 3 sax cement with dump bailer,

sand to 3160', set 5 sax cement with dump bailer, pulled 1000'

7" - filled hole with mud to 160', set rock bridge and 20 sax

cement, mud to 30', set rock and 10 sax cement to bottom cellar.

**PLUGGING**  
FILE SEC 12 T 9 R 17W  
BOOK PAGE 141 LINE 9

**RECEIVED**  
STATE CORPORATION COMMISSION  
AUG 9 X 1955  
CONSERVATION DIVISION  
Wichita, Kansas

*8/9/55*

*Edwin Kelly*  
District Conservation Agent  
Date 8-5-55