

15-163-19241-00-00

*B*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 95-4

LOCATION CSE SW

SEC. 12 TWP. 9 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Mc Clay

Operator Co Op Refg Assn Address 765 Great Bend, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3350 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 192' circulated with cement - 5 1/2" at 3320' with  
200 sax cement behind - Lane Wells plugs at 3125' - perforations  
at 3120' - 5 1/2" squeezed with cement at 774'.

Filled with chat to 3100', set 4 sax cement with dump bailer,  
pulled 385' 5 1/2" - filled with mud to 190', set rock bridge  
and 15 sax cement - mud to 35', set rock and 10 sax cement  
to bottom cellar.

*5/27/53*

REC'D  
STATE CORPORATION  
MAY 2 1953

*Edmond Jones*  
District Conservation Agent

Date 5-26-53

**PLUGGING**  
FILE SEC 12 T 9 R 17W  
BOOK PAGE 25 LINE 4

CONSERVATION DIVISION  
Wichita, Kansas