

15-163-19242-00-01

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT**RECEIVED**
STATE CORPORATION COMMISSIONJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

FEB 3 1964

2/3/64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cooperative Refining Assn

Complete Address: Drawer (C) Great Bend, Kans

Lease Name Mc Clay Well No. 1

Location E $\frac{1}{2}$ SW SW Sec. 12 Twp. 19 Rge. 9 (E) 1 (W) 17

County Rooks Total Depth 3347

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Halliburton Cementing Co

Address: License No.

Operation Completed: Hour 6PM Day 31 Month 1 Year 64

The Above well was plugged as follows:

8 5/8" 212' circulated with cement - 5 1/2" 3185' with 150 sax cement -
~~4 1/2" liner cemented in 3262' to 3168' - 5 1/2" squeezed in Dakota with cement~~
 amount ?

Attempted to recondition hole with rotary - bit went out of pipe at
 924' - pipe disentergrated - circulated hole with heavy drilling mud
 through 2 1/2" drill pipe - displaced 50 sax cement through 2 1/2" at 924' -
 heavy mud to 430' - displaced 25 sax cement through 2 1/2" at 430' - heavy
 mud to 140' - displaced 20 sax cement through 2 1/2" at 140' - cement settled
 to 30' - filled with cement 30' to 0' by hand - Pumped and squeezed
 heavy drilling mud in 8 5/8" - 5 1/2" annulus at 300# pump pressure -
 no pipe recovery.

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICEDSigned: E. J. Kelly
Well Plugging SupervisorDATE 2/6/64
INV. NO. 8595-W