

DISTRICT CONSERVATION AGENT'S REPORT
15-163-00730-00-00

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 137-3

LOCATION NE NE SE

SEC. 1 TWP. 9 RGE. 18

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Betts

Operator H. W. Patton Address c/o Murfin DrgbCo
Wichita, Kans

Field _____ County Rooks

Total Depth 3440 Feet.

Plugging Contractor J & M Casing Pulling

Plugging Contractor's License No. 11

Address _____
(Describe briefly the manner in which the well was plugged)

8 5/8" at 210' circulated with cement - 5 1/2" at 3420' with
75 sax cement behind - Lane Wells plugs to 3360', perforations at
3340'.

Filled with chat to 3320', set 4 sax cement with dump bailer,
pulled 2700' 5 1/2" - filled with mud to 200', set rock and 15
sax cement, mud to 35', set rock and 10 sax cement to bottom
cellar.

PLUGGING
FILE SEC 1 T 9 R 18W
BOOK PAGE 137 LINE 3

RECEIVED
COMMISSION
AUG 1 X 1955
Date 7-28-55
District Conservation Agent
Eldon Patton
CONSERVATION DIVISION
Wichita, Kansas

8-1-55