

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20532-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
SEP 5 1974
CONSERVATION DIVISION
Wichita, Kansas

95-74

Operator's Full Name Black Petroleum Co.

Complete Address Suite 545 Olive W. Garvey Bldg. Wichita Ks.

Lease Name J. Thomas Well No. 1

Location NW-NW-NW Sec. 1 Twp. 9-S Rge. 18 (E) (W)

County Rooks Total Depth 3492

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilg. Co Rig #5 Walter Oden Driller

Address 1720 Wichita Plaza Wichita Ks. License No.

Operation Completed: Hour 6:45 PM Day 3 Month 9 Year 1974

The above well was plugged as follows:

Map Dakota Top Sea level +1475 K.B. Elev. + 2038
223' of 8 5/8 surface Pipe - pumped Through Drill Stem.
10 sacks cement 50/50 portmix 6% gel @ 720'
20 " " " " " " @ 220'
push wooden Plug to 40'
Dump 1/2 sack Hulls on top of Plug
Fill to cellar with 10 sacks cement 50/50 portmix 6% gel.
Allied pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ralph Balthasar
Well Plugging Supervisor

DATE 9/5/74
INV. NO. 9840-W