

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED

OCT 25 1960

CONSERVATION DIVISION
Wichita, Kansas

1025-60

15-163-00784-00-00

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: _____ Rooks
Location: NW SW SW Sec. 9 Twp. 9 Rge. 18 (E) (W)
Name of Field: _____ Total Depth: 3575

I have this date completed supervision of plugging of:

Lease Name: Holl Well No. 1

Operator's Full Name: W. H. Pitts

Complete Address: 413 Park View Ave. Jonesboro, Arkansas

Plugging Contractor: Peel Bros Drig Co

Address: Hoisington, Kans License No. _____

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 3PM Day 22 Month 10 Year 60

The above well was plugged as follows:

8 5/8" 220' circulated with cement.

Circulated hole with heavy mud, set cementing plug at 550', displaced
20 sax cement through drill pipe, heavy mud to 180', set cementing plug
and 15 sax cement, heavy mud to 40', set plug, bridge and 10 sax cement
to bottom cellar.

Signed: *Edon Petty*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

INVOICED
DATE 11/14/60
INV. NO. 2156-W