

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20242-00-00

RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1969
CONSERVATION DIVISION
Wichita, Kansas

8-25-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name L ANDES Exp. Co. & Sentinal Res. Corp.

Complete Address Box 867 Magnolia, Ark.

Lease Name O'Brien Well No. 1

Location NW NW SE Sec. 11 Twp. 9 Rge. (E) (W) 18

County Rooks Total Depth 3590

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Hellar Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 8:15P Day 22 Month 8 Year 1969

The above well was plugged as follows:

RTD 3590' 8 5/8 csg set at 215' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gun pits, circulate heavy mud, set cementing plug at 660' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 210' set cmtplug and displaced 20 sk cmt thru drill

pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Murray
Well Plugging Supervisor

DATE 8/26/69
INV. NO. 370-W