

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

8-31-61
RECEIVED
STATE CORPORATION COMMISSION
AUG 31 1961
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-163-00792-00-01

File No. _____ County: Rooks
Location: NE NE NE Sec. 14 Twp. 9 Rge. _____ (E) _____ (W) 18
Name of Field: _____ Total Depth: 3580

I have this date completed supervision of plugging of:

Lease Name: O'Brien Well No. 1

Operator's Full Name: Bergman Drg Co

Complete Address: 425 Union Center Wichita, Kansas

Plugging Contractor: Wilson Pipe Pulling

Address: Stafford, Kansas License No. 375

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 2PM Day 25 Month 8 Year 61

The above well was plugged as follows:

8 5/8" 213' circulated with cement. 5 1/2" 3579' with 100 sax cement -

Perf 3509'

Filled with sand to 3490', set 4 sax cement with dump bailer, pulled 5 1/2"
to 550', circulated hole with heavy gel mud through 5 1/2" at 550' (18 sax Ge
displaced 20 sax cement through 5 1/2" at 550', heavy mud to 200', displaced
20 sax cement through 5 1/2" at 200', heavy mud to 35', set bridge and 10 sax
cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: *Edson Peety*
Conservation Division Agent

Reviewed: *Harold Hollis*
Field Supervisor

Remarks:

INVOICED
DATE 9/8/61
INV. NO. 3405-W