

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-19013-00-00<sup>01</sup>  
Spot: SESENW Sec/Twnshp/Rge: 11-9S-16W  
2970 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: LIVINGOOD Well Number: 1  
County: ROOKS Total Vertical Depth: 3286 feet

Operator License No.: 100  
Op Name: KANSAS CORPORATION COMMISSION  
Address: 130 S MARKET RM 2078  
WICHITA, KS 67202

Conductor Pipe: Size 13.375 feet: 755  
Surface Casing: Size 8.625 feet: 2035  
Production: Size 7 feet: 3286  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/18/2001 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Plugging Method: Ordered out 425 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 01/18/2001 11:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to top of fish 680'.  
Allied pumped 110 sxs 60/40 pozmix - 10% gel - cement circulated.  
PTOH. Allied squeezed with 315 sxs with 700# hulls.  
Max. P.S.I. 650#. S.I.P. 300#.

2/5/01  
RECEIVED  
STATE CORPORATION COMMISSION

FEB - 5 2001

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY

Plugged through: TBG

District: 04

HO

Signed

Richard Williams

(TECHNICIAN)

BROADVIEW OIL CO

#1 LIVINGOOD

11-9-16W  
SE SE NW

Contr.

ROOKS County

E 2072

Comm 6-26-38

Comp 9-21-38

IP

519 BOPD  
GR 42

Tops	Depth	Datum
ANH	1298	
TOP	2938	
LANS	3212	
TD	3286	

Casing  
13" 755  
8" 2035  
7" 3240

OWDD  
Comp 8-20-40  
OTD - 3250  
A/8000


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

9  
12  
21