

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19014-00-00
Spot: W2SWNW Sec/Twnshp/Rge: 11-9S-16W
3300 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: LIVINGOOD Well Number: 9
County: ROOKS Total Vertical Depth: 3375 feet

Operator License No.: 100
Op Name: KANSAS CORPORATION COMMISSION
Address: 130 S MARKET RM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 230
Production: Size 4.5 feet: 3374
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/16/2001 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/16/2001 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

4 1/2" casing set at 3374'. Perforations 3132' - 3230'.
Rods and tubing stuck in the hole. Gas pressure on backside.
3/4" rod parted at 1175'. 2 7/8" tubing parted at 1425'.
Allied pumped 30 sxs 60/40 pozmix - 10% gel with 200# hulls down 8 5/8" annulus. Max. P.S.I. 100#.
Blew hole in surface pipe below head.
Tied onto 4 1/2" casing cement and circulating.
Called welder and patched surface pipe.
Allied pumped a total of 300 sxs 60/40 pozmix - 10% gel with 500# hulls.
Max. P.S.I. 500#. S.I.P. 200#.

2/5/01
RECEIVED
STATE CORPORATION COMMISSION
FEB - 5 2001
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

BROADVIEW OIL CO

19 LIVIUGOOD

11 9-16W
4 5 1/2 N 1/2

Contr. SUFFLDS DRILG

ROOKS

County

E 2007KB Comm. 3/10/63 Comp. 3/21/63 IP 25 BOPD (OWWF)

(LANS 3132-3230)

LOG Tops	Depth	Datum
TOP	2852	-848
HEEB	3078	-1071
TOR	3099	-1092
LANS	3121	-1114
LTD	3342	-1335
RTD	3375	-1368

Casing

8" 250:

4" 3374:

NO TESTS:

CO: PF 1/3136: 1/3162: 1/3177:
 1/3188: 1/3216: A 1000 & FLUSH
 75 BW: 24/3222-30: 28/3212-20:
 25/3186-94: 25/3174-82: 25/
 3157-65: 12/3142-46: 16/3132-37:
 POP:

LATON

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS