

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19015-00-00
Spot: S2SWNE Sec/Twnshp/Rge: 11-9S-16W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: LIVINGOOD C Well Number: 5
County: ROOKS Total Vertical Depth: 3475 feet

Operator License No.: 100
Op Name: KANSAS CORPORATION COMMISSION
Address: 130 S MARKET RM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 274 W/260 SXS
Production: Size 4.5 feet: 3474 W/150 SXS
Liner: Size feet:

Well Type: EOR UIC Docket No: E11184.2 Date/Time to Plug: 01/23/2001 3:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTRYE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2026

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 500# hulls.
Squeezed at 871' w/125 sxs. 2044' - 2106' w/200 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/24/2001 6:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Unable to get 1 1/2" x 4 1/2" packer loose - circulated fresh water to pit with approximately 10 gallons drilling mud.
Ran wireline to 3096'. Attempted to shoot tubing off - still stuck.
Allied pumped 50 sxs 60/40 pozmix down 1 1/2" tubing and displaced to 2900'.
Ran wireline to 1034' and shot tubing free.
Allied pumped 100 sxs cement.
PTOH. Cement at 400' on backside of tubing.
Topped 4 1/2" casing off on January 25, 2001, with 25 sxs.
Pumped 50 sxs down backside with 200# hulls.
Max. P.S.I. 500#. S.I.P. 400#.

2/5/01
RECEIVED
STATE CORPORATION COMMISSION
FEB - 5 2001

Remarks: ALLIED CEMENTING COMPANY.

CONSERVATION DIVISION
Wichita, Kansas

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

FEB 01 2001

BROADVIEW OIL CO.

#5 LIVINGOOD 'C'

11-9-16W
S2 SW NE

Contr. SHIELDS DRILLING

ROOKS County

E 2075KB Comm 4/9/63 Comp. 4/25/63 IP PMP 30 B0 + 60 BWP
LANS 3214-3412

SMP Tops	Depth	Datum
TOP	2950	-875
HEEB	3175	-1100
TOR	3194	-1119
LANS	3213	-1138
B/KC	3472	-1397
TD	3475	-1400

Casing

8" 274/260 SX:
4" 3474/150 SX:
NO TESTS:
NO CORES:

CO 3445: 12/3408-12: /3402-04:
/3396-3400: /3381-87: /3368-72:
/3358-64: /3306-26: /3266-74:
/3250-56: /3236-40: /3226-30:
/3214-16: A 12000: POP:

LATON

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS