

To: **6 040952**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-27 421 R
API NUMBER **15-163-19194-00-01**
SW SE, SEC. **11**, T **9**, S, R **16** W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # **7802**
Operator: **Rider Oil and Gas Inc.**
Name & Address **2805 Bent Bay Circle**
Wichita, Ks. 67204

_____ feet from S section line
_____ feet from E section line
Lease Name **Luhman** Well # **1**
County **Rooks** **109.23**
Well Total Depth **3361** feet
Conductor Pipe: Size _____ feet
Surface Casing: Size **None** feet

Abandoned Oil Well ☒ Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor **Allied Cementing** License Number _____

Address **Russell, Ks.**

Company to plug at: Hour: **9:00AM** Day: **26** Month: **Sept** Year: 19 **88**

Plugging proposal received from **Don Rider**

(company name) **Rider Oil and Gas** (phone) _____

were: **6 5/8" casing set at 2898 w/cement N.A.. 5 1/2" casing set at 3228' w/cement**

N.A. P.B. w/sand to 3175' and 5 sks cement. Shot casing at 1800'. Shot

casing at 800' and recovered same. Ordered 600 sks cmt 60/40 Poz 8% Gel w/

1/4# F.C.

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1988

Plugging Proposal Received by **Dennis L. Hamel**
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part _____ None _____

Operations Completed **Wichita, Kansas** Hour: **10:00AM** Day: **27** Month: **Sept** Year: 19 **88**

ACTUAL PLUGGING REPORT **Sept 26, 1988 Shot base Dakota at 800'. Shot top**

Dakota at 400'. Ran tubing to 800'. Circ cement to surf. w/250 sks .

Pulled tubing. Tied on 6 5/8" casing sq. additional 250 sks cement in casing

(400# Psi). Disp cement to 100' w/water. Shut down: Sept 27, 1988.

Perf casing at 100' Pemped additional 100 sks cement to circ. at surface.

Job completed.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

Signed **Dennis L. Hamel**
Dennis L. Hamel (TECHNICIAN)

DATE **11-10-88**

INV. NO. **22973**