

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-19196-00-01
C-N1/2
NW-NE, Sec. 11, T 9 S, R 16 WE

_____ feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

_____ feet from W/E section line

Operator License # 6033

Lease Name LIVINGOOD Well # C-4

Operator: MURFIN DRILLING CO.
Name & Address 617 UNION CTR.
WICHITA, KANSAS
67202

County ROOKS

Well Total Depth 3460 feet \$112.45

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON OMT. License Number _____

Address 1100 EAST 8th ST. HAYS, KANSAS 67601

Company to plug at: Hour: 12:50 PM Day: 7th Month: JUNE Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO BILL BROWN.

(company name) MURFIN DRILLING CO. (phone) 316-267-3241

were: 8 5/8" - 260' SR. CUL, 4 1/2" SET @ 3459' w/ ? OMT.
SQUEEZED @ 869' to 933' w/ 125' OMT, TUBING FISH @ 970' EI
TOP PERK'S 3220' NO 4 1/2" CSG. RECOVERY

ORDER 400' HALLIBURTON LIGHT, 1' FLO-CELE, 5' HULL'S AND 4 1/2" PLUG
PUMP OMT. IN ANNULUS AND 4 1/2" CSG. WITH PUMP TRUCK

Signed Maurice Schmidt
(TECHNICIAN) (0010)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:50 PM Day: 7th Month: JUNE Year: 19 83

ACTUAL PLUGGING REPORT ORDERED 400' HALLIBURTON LIGHT, 5' HULL'S
1' FLO CELE AND 4 1/2" PLUG, PUMPED IN WITH PUMP TRUCK.
PUMPED IN ANNULUS 115' OMT. 2' HULL'S, MAX. PRESSURE 450 PSI
PUMPED IN 4 1/2" CSG. 285' OMT. w/ 3' HULL'S AND
1' FLO-CELE, AND 4 1/2" PLUG. MAX. PRESSURE 750 PSI
SHUT IN AT 500 PSI CEMENTED BY HALLIBURTON OMT.

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~do~~) observe this plugging.

Signed Maurice Schmidt
(TECHNICIAN) (0010)

RECEIVED
STATE CORPORATION COMMISSION

FORM CP-2/3
Rev. 9-82

JUN 17 1983

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 6-24-83
INV. NO. 6670-W