

3-24-88

6 061460

API NUMBER 15-163-01463-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE NW NE, SEC. 21, T 9 S, R 16 (W/E)

TECHNICIAN'S PLUGGING REPORT

Operator License # 8914

Lease Name Casey Well # #2

Operator: H & C Aie Operating, Inc

County Rooks 111.31

Name & Address P. O. Box 86

Well Total Depth 3425 feet

Plainville, Kansas 67663

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 158 w/ 125 sx

Abandoned Oil Well X Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Co Tools & B. J. Titan License Number

Address

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Herman Fellhoelter

(company name) H. C. Aie Operating (phone)

were: Dakota Squeezed from 835' to 150' w/ 100sx. Holes in Anhydrite at 1310'.

Plugging Proposal Received by GPK

(TECHNICIAN)  
Gilbert P. Leiker

Plugging Operations attended by Agent?: All XX Part None

Operations Completed: Hour: 12:00 noon Day: 24 Month: March Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set @ 158' w/125 sx, 5 1/2" set at 3418' w/ 150 sx.

Top perf at 3182". Pumped down 8 5/8" w/50 sx common to 500 lbs pressure and 300 lbs standing pressure. Pumped down the 5 1/2" w/25 sx common cement and 275 sx econolite with holes in the anhydrite. 400 lbs pressure and 200 lbs shut in pressure. Tried to pump down 8 5/8" again with immediate 800 lbs pressure.

JUL 20 1988 7/20/88

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-25-88

Signed Gilbert Leiker by DLP  
(TECHNICIAN)  
Gilbert P. Leiker

INV. NO. 21638