

15-103-03641-00-01
S-21

2100

6 062158

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- E-9161
NE, SEC. 21, T 9 S, R 16 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Operator: Oxy USA Inc.
Name & Address: Box 26100
Oklahoma City, Ok.
73126-0100

3300 feet from S section line
990 feet from E section line

Lease Name Don Unit Well # 903 W

County Rooks 112.78

Well Total Depth 3470 P.T. 3426 feet

Conductor Pipe: Size feet

Surface Casing: Size 9 5/8 feet 246

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Ostrum Well Service Inc. License Number 5680

Address R. R. 1 Box 368 Plainville, Ks. 67663

Company to plug at: Hour: 11:00 AM Day: 21 Month: May Year: 19 90

Plugging proposal received from Don Sheldon

(company name) Oxy USA Inc. (phone)

were: Order 50 sks common 300 sks 65/35 poz 6% gel 5 sks hulls and 100 sks for 9 5/8".

Well had been sq w/500 sks cement from 1200' to surface at 400' - 900' - 1200'.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 12:30 PM Day: 21 Month: May Year: 19 90

ACTUAL PLUGGING REPORT 9 5/8" set at 246' w/170 sks. 5 1/2" set at 3470' w/85 sks.

Top perf at 3184'. Pumped in 5 1/2 50 sks common followed w/150 sks 65/35 poz 6% gel

followed w/10 sks hulls in 190 sks cement w/600 psi. 9 5/8" - 60 sks cement w/400 psi.

Remarks: By Halliburton
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-27-90

INV. NO. 28497

observe this plugging.

JUN 20 1990

CONSERVATION DIVISION
Wichita, Kansas

Signed Gilbert G. Scheck
(TECHNICIAN)