

4-041468

6-16

15-163-01491-00-00

API number: 15- - 5-20-49

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SE SE /4 SEC. 09 , 09 S, 17 W
330 feet from S section line
330 feet from E section line

Operator license# 3456

Lease Thompson well # 3

Operator: A.F.G. Energy, Inc.

County Rooks

Address: P.O. Box 458
Hays, Kansas 67601-0458

Well total depth 3489 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4 Inch @ 26 feet
w/20 sx.

113.39

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 16 Month: June Year: 93

Plugging proposal received from: Terry Piesker

Company: A.F.G. Energy, Inc. Phone: 913-625-6374

Were: 5 1/2" casing set @ 3487' w/150 sx. cement. Perf. @ 3458'- 3340'.
Squeezed @ 1736' w/75 sx. common. Squeezed @ 1705' w/75 sx. cement.
Tagged T.O.C. @ 1028'. Additional squeeze @ 624' w/100 sx. cement
circulate to surface. Re-tested casing, found holes in casing from
165' to 800'. Ordered 150 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C.

Plugging Proposal Received by: Don Butcher - Dennis Hamel
Plugging operations attended by agent? All , Part , None

Completed: Hour: 10:15A.M. , Day: 16 , Month: June , Year: 93

Actual plugging report: R.I.H. with tubing to 955'. Spotted 80 sx.
cement to circulate to surface. P.O.O.H. with tubing, squeezed 20 sx.
cement down casing. Max. 500 P.S.I. S.I.P. 500#.

Remarks: _____
Condition of casing(in hole): GOOD _____ BAD Anhy. plug: YES NO _____
Bottom plug(in place): YES , CALC _____ , NO _____ Dakota plug: YES , NO _____
Plugged through TUBING , CASING _____ . Elevation: _____ GL _____

I did / did not observe the plugging.

Dennis L. Hamel RECEIVED
STATE CORPORATION COMMISSION

DATE 7-9-93
INV. NO. 38077

(agent) JUN 30 1993
Form CP-273

6/30/93

CONSERVATION DIVISION
Wichita, Kansas