

To: 6030555
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5398

Operator: ARCO OIL & GAS CO.

Name & Address BOX 521

TULSA OKLAHOMA

74102

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor ALLIED CMT CO License Number

Address PLAINVILLE

Company to plug at: Hour: Day: 3 Month: 8 Year: 19 85

Plugging proposal received from BOB MCGINN

(company name) ARCO OIL & GAS CO. (phone)

were: 10 3/4 SET @ 105 CWC 7" SET @ 3154 W/125 SX. 5 1/2" LINER FROM 3115 TO 3313'
5 1/2" LINER FROM SURFACE TO 1022' HOLE @ 1128' ORDER 60/5002 2 1/2 GEL.
RUN TUBING TO BOTTOM Pump CMT. MIX. ALLIED CMT. CO

Plugging Proposal Received by Carl Goodnow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 6:30 PM Day: 3 Month: 9 Year: 19 85

8-29-85 1st DAY
ACTUAL PLUGGING REPORT TAG WIRELINE 3225' TAG TUBING 3147' Pump 320 SX. 8 SX HULL

CMT. MIX 2nd DAY 8-30-85 TAG CMT @ 3225' Pump 150 SX. 8 SX. HULLS WAIT 2 Hrs.

TAG. 3015' Pump 8 SX. HULLS 150 SX. CMT. MIX. LAYDOWN WAIT TILL 9-3-85

TAG CMT @ 2147' Pump 150 SX. CMT MIX 6 SX. HULLS WAIT 2 Hrs. TAG CMT @

1250 Pump 140 SX. CMT. MIX. CWC. LAYDOWN PIPE LOAD HOLE HOLE STAYED

FULL Pump Down 10 3/4" - 7" ANNULUS 100 SX. CMT. MIX Pump Down 7" 5 1/2" ANNULUS

Remarks: 110 SX. CMT. MIX. LOADED ALL PIPE NO URE. PLUG. COMPLETE.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE SEP 10 1985

INV. NO. 10002

RECEIVED
STATE CORPORATION COMMISSION

SEP 9 1985

CONSERVATION DIVISION
Wichita, Kansas

Signed Carl Goodnow
(TECHNICIAN)

FORM CP-2/3
Rev. 01-84