

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-22,332-00-00
SW 1/4, Sec. 16, T 9 S, R 18 W 1/4
1540 feet from N/S section line
440 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Stahl Well # 1-16

Operator: Murfin Drilling Company
Name & 250 N. Water Suite 300
Address Wichita, Ks. 67202

County Rooks

Well Total Depth 3589 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 265

116.65

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drlg. Company License Number 6033 Tag # 604

Address 220 N. Water Suite 300, Wichita, Ks. 67202

Company to plug at: Hour: 1 PM Day: 12 Month: April Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Lloyd Dellelette

(company name) Murfin Drlg. Company Inc. (phone) (316) 267-3241

were: 8 5/8" 265' S.P. CUC w/165 sks quick set (by Allied Cmt.) Ordered 195 sks

50/50 pozmix 6% gel 3% cal. cl. - 1 sk cello-flake and 8 5/8" plug. Spot with drill stem, turn hole over, heavy mud between all plugs. No circulation problems, no ar buckle, conglomerate Elev. 2094' Anhy 1436

Signed *Murray Schmidt*
DOIC (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:15 PM Day: 12th Month: April Year: 1984

ACTUAL PLUGGING REPORT Ordered 195 sks 50/50 pozmix 6% gel 3% cal. cl. - 1 sk cello flake, and 8 5/8" plug. Turned hole over, spotted with drill stem - heavy mud between all plugs.

1st plug @ 1440' w/25 sks cmt

2nd plug @ 870' w/100 sks cmt. w/1 sk cello-flake

3rd plug @ 270' w/50 sks cmt

4th plug solid bridge hull's and plug @ 40' to 0 w/10 sks cmt

Remarks: 10 sks in Rat Hole (circulate)
Cemented by Allied Cmt.

4-23-84
RECEIVED
STATE CORPORATION COMMISSION
APR 23 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

Signed *Murray Schmidt*
DOIC (TECHNICIAN)

INVOICED

DATE: 4-23-84

INV. NO. 1232 4-12 APR 26 1984