

6-3 15-163-01544-00-957

6 041299

API NUMBER 15- 5-30-56

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SW NW, SEC. 19, T. 9 S, R. 18 W/E R

3630 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5846 384V

Lease Name Hilgers 'A' Well # 2

Operator: T.O. Rush

County Rooks 116.67

Name & Address 2301 Ida Lane

Well Total Depth 3590 feet

Hays, Kansas 67601

Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8 feet 140'w/135 sx.

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address Russell, Kansas

Company to plug at: Hour: 10:00 A.M. Day: 3 Month: 6 Year: 19 91

Plugging proposal received from Tom Rush

(company name) T.O. Rush Oil (phone)

were: 5 1/2" csg set at 3573' w/125 sks cmt: perfs at 3312' to 3336: Perf anhy at 1550-52, perf base dakota at 850-52'. Ordered 200 sx: 60/40 poz. 4% gel to plug bottom, plus ordered 250 sks 60/40 poz. 10% gel w/1 lb flocele plus 5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 8:00 P.M. Day: 3 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT Plug bottom: set packer @ 2670'; squeezed 200 sx. cmt. at

bottom, Max 500# (Allied Cmtg-#2120) R.I.H. w/tubing to 1600'; spot 100 sx. cmt;

pull upto 860'; spot 50 sx. cmt; pull up to 500'; spot 20 sx. cmt. to circulate at

surface: Pull out of hole w/tubing: Hook up to 5 1/2" csg.; squeezed 50 sx. cmt:

Mixed 500# hulls in cmt. Hooked-up to 8 5/8 surface pipe - pumped 40 sx. cmt.

Max 400#.

Remarks: Packer in hole below 2670'

(If additional description is necessary, use BACK of this form.) CONSERVATION DIVISION Wichita, Kansas

INVOICED

DATE 6-8-91

INV. NO. 32256

Signed Dennis L. Hamel (TECHNICIAN)

RECEIVED
6-13-91
JUN 13 1991

SEP 27 1991