


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County, Sec. 24 Twp. 9 Rge. 21 ~~XX~~ (W)

Location as "NE/CNW/SW" or footage from lines SE NW SE
Lease Owner Murfin Drilling Company
Lease Name Gochran Cockran & Co Well No. 1
Office Address Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 3 19 57
Application for plugging filed May 3 19 57
Application for plugging approved May 3 19 57
Plugging commenced May 3 19 57
Plugging completed May 3 19 57
Reason for abandonment of well or producing formation Non-productive



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3518 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	164	8-5/8"	164	None-cement circulated

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug at 550', 20 sacks cement through drill pipe.
Mud to 40', plug at 40', one-half sack hulls, 10 sacks cement to top of hole.

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1957

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Mallonee Drilling Company, Inc.
Address 820 Union Center, Wichita, Kansas

CONSERVATION DIVISION
WICHITA, KANSAS

STATE OF Kansas COUNTY OF Sedgwick, ss: R. E. Mallonee (employee of owner) or (owner or operator) contractor of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) R. E. Mallonee
Union Center, Wichita, Kansas (Address)

6-19-57

SUBSCRIBED AND SWORN to before me this 18th day of June, 19 57

My commission expires December 14, 1957

Martha Boyer
Notary Public.



PLUGGING
FILE SEC. 24 T. 9 R. 21W
BOOK PAGE 11 LINE 19

15-065-02359-00-00

DRILLERS' LOG
#1 Cochran Cockran ^{KCC}
SE 1/4 SE Sec. 14-98-21W ^{ZAP}
Graham County, Kansas

OPERATOR: Murfin Drilling Company
CONTRACTOR: Mallonee Drilling Company, Inc.

Commenced: 4-11-57
Completed: 5-3-57

FROM	TO	DESCRIPTION	REMARKS
0	40	Surface soil and clay	Elevation 2257 RB
40	140	Shale and sand	
140	164	Shale and shells	8 5/8" casing set at 164' with 115 sacks common and 1 sack calcium chloride. Cement circulated.
164	670	Shale	
670	720	Sand and shale	
720	860	Shale	
860	1460	Shale and shells	
1460	1755	Shale, shells and red bed	
1755	1805	Anhydrite	
1805	2230	Shale and shells	
2230	2460	Lime and shale	
2460	2525	Lime	
2525	2695	Lime and shale	
2695	2785	Lime	
2785	2815	Shale and lime	
2815	3140	Shale and shells	
3140	3175	Lime and shale	
3175	3440	Lime	
3440	3477	Lime and shale	
3477	3818	Lime	
3818		Total Depth of Hole	N & A

I certify that to the best of my knowledge and belief, the above represents a true and accurate Drillers' log record of the captioned well.

R. E. Mallonee

R. E. Mallonee

State of Kansas)
) ss:
County of Sedgewick)

Subscribed and sworn to before me this 14th day of May, 1957.

PLUGGING			
FILE	SEC 24	T 9	R 21W
BOOK	PAGE 11	LINE 19	

Joan McCann

Joan McCann, Notary Public

My commission expires: May 9, 1959

JUN 10 1957
6-19-57
CONSERVATION DIVISION
Wichita, Kansas