

15-065-02541-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Graham County, Sec. 24 Twp. 2S. Rge. 21 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW $\frac{1}{2}$, NE $\frac{1}{2}$, NW $\frac{1}{2}$
Lease Owner Barnett Drilling, Inc., et al.
Lease Name Balthazor Well No. 2
Office Address 623 First National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 30, 19 51
Application for plugging filed August 30, 19 51
Application for plugging approved August 30, 19 51
Plugging commenced August 30, 19 51
Plugging completed August 30, 19 51
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3,760 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Pipe		0	160 Ft.	8 5/8"	160 Ft.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3,760 feet to 155 feet. Filled with $\frac{1}{2}$ sack of hulls and 15 sacks of cement to 115 feet. Filled with heavy mud to 40 feet and set top wooden plug at 40 feet. Dumped $\frac{1}{2}$ sack of hulls on plug and filled to bottom of cellar with 10 sacks of cement.


RECEIVED
SEP 6 X 1951

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Barnett Drilling, Inc.,
Address 623 First National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
E. R. Stubblefield (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. R. Stubblefield*
623 First National Bank Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of September, 19 51
My commission expires May 12, 1955
Adelaide Olivier
Notary Public.



PLUGGING
FILE SEC 24T-9-R21W
BOOK PAGE 127 LINE 19

28-5091-s 8-50-10M

BARNETT DRILLING, INC., ET AL
LOG OF BALTHAZOR WELL NO. 2
NW 1/4 NE 1/4 NW 1/4 SECTION 24-9S-21W, GRAHAM COUNTY, KANSAS

DATE COMMENCED: August 19, 1951

DATE COMPLETED: August 30, 1951

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay	0	40'	
Sand	40'	58'	
Shale and Shells	58'	160'	
			Set 8 5/8" Surface pipe @ 160 feet; cemented with 125 sacks.
Shale	160'	660'	
Shale and Shells	660'	1,275'	
Sand	1,275'	1,345'	
Shale and Shells	1,345'	1,545'	
Sand	1,545'	1,625'	
Red Bed	1,625'	1,685'	
Anhydrite	1,685'	1,720'	
Shale and Shells	1,720'	2,200'	
Lime and Shale	2,200'	2,270'	
Lime	2,270'	2,345'	
Lime and Shale	2,345'	3,455'	
Lime	3,455'	3,615'	
Lime and Shale	3,615'	3,655'	
Lime	3,655'	3,712'	
Conglomerate and Chert	3,712'	3,727'	
Conglomerate	3,727'	3,760'	
		3,760'	Dry and abandoned.

Certificate

I, W. E. Cruce, of Barnett Drilling, Inc., hereby certify that to the best of my knowledge and belief, the above is a true and correct log of the Balthazor Well No. 2, located in the NW 1/4 NE 1/4 NW 1/4 of Section 24-9S-21W, Graham County, Kansas.

W. E. Cruce

Subscribed and sworn to before me, in and for the County of Sedgwick, State of Kansas, this 5th day of September, 1951.

Adelaide Olivier
Notary Public

STATE OF KANSAS

My Commission Expires: May 12, 1955

9-6-51

PLUGGING
 24-9-21W
 FOOT 107-14