


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-065-01496-00-00
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Graham County, Sec. 25 Twp. 9 Rge. 21 (E) W (W)
Location as "NE/CNW*SW*" or footage from lines NW NW SW
Lease Owner Morgenstern & Specter, Inc.
Lease Name Raymond Teall "B" Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 1-29-49 19
Application for plugging filed April 2, 1962 19
Application for plugging approved April 3, 1962 19
Plugging commenced 4-2-62 19
Plugging completed 4-17-62 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Depth to top 3821 Bottom 3821 Total Depth of Well 3821 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	183'	None
				5-1/2"	3809'	1287'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3821', sanded to 3810' and dumped 4 sacks of cement @ 3810' with dump bailer. Pulled 5 1/2" to 525' and circulated pipe with 30 sacks of jull mud and pumped in 20 sacks of cement. Pulled 5 1/2" casing to 160' and pumped in 20 sacks of cement. Pulled balance of 5 1/2" casing, bailed mud to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAY 10 1962

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

Name of Plugging Contractor Knight Casing Pulling Company 5-10-62
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas

SUBSCRIBED AND SWORN TO before me this 19th day of April, 1962

My commission expires May 20, 1964

Milton J. Volin
Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

412 Union National Bk. Bldg., Wichita, Kansas

15-065-01496-00-00

COPY

Company - B & R DRILLING, INC
Farm - Teall "B" No. 1

SEC. 25 T. 9 Q. 21W
NW NW SW

Total Depth. 3821'

Comm. 1-15-49

Comp. 1-29-49


Shot or Treated.

Contractor.

Issued. 4-23-49

County. Graham

KANSAS



CASING:

8 5/8" 183' cem. w/125 sx
5 1/2" 3819' cem. w/ 75 sx

Elevation. _____

Production. 87 bbl

Figures indicate Bottom of Formations.

surface clay	20
sand, shells	60
shale, shells	184
shale	245
shale, shells	750
shale	1080
shale, sand, pyrite	1160
shale, shells	1205
sand, shale	1460
shale, red rock	1550
shale, red rock	1730
anhydrite	1760
anhydrite	1780
red shale, shells	1935
shale, shells	2270
lime, shale	3455
lime	3821
Total Depth	

RECEIVED
STATE CORPORATION COMMISSION

APR 3 1962
4-3-62
CONSERVATION DIVISION
Wichita, Kansas