

15-065-00204-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Graham County, Sec. 12 Twp. 9S Rge. (E) 22 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE $\frac{1}{4}$  SE $\frac{1}{4}$  SW $\frac{1}{4}$   
Lease Owner Barnett Drilling, Inc., et al  
Lease Name Vesper Well No. 1  
Office Address 417 First Nat'l Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 10 19 51  
Application for plugging filed January 10 19 51  
Application for plugging approved January 10 19 51  
Plugging commenced January 10 19 51  
Plugging completed January 10 19 51  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production - 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 3896 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Casing				8 5/8"	162 ft.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3896 feet to 162 feet. Set wooden plug at 162 feet.  
Filled surface casing with 1 sack of hulls and 15 sacks of cement to 115 feet. Filled surface casing with heavy mud from 115 feet to 35 feet. Set wooden plug at 35 feet and filled surface casing with 1/2 sack of hulls and 10 sacks of cement to bottom of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 30 1951  
CONSERVATION DIVISION  
Wichita, Kansas

1-30-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to  
Address Barnett Drilling, Inc.  
417 First Nat'l Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
W. R. Hunter (employee of owner) of the above-described well,


being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. R. Hunter

417 First Nat'l Bank Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 23rd day of January, 1951.  
My commission expires May 12, 1951.  
Adelaide Chivers Notary Public.

PLUGGING  
FILE SEC 1219 R22  
BOOK PAGE 58 LINE 41



15-065-00204-00-00

BARNETT DRILLING, INC., ET AL

LOG OF VESPER WELL NO. 1

SE<sup>1</sup>/<sub>4</sub> SE<sup>1</sup>/<sub>4</sub> SW<sup>1</sup>/<sub>4</sub> SECTION 12-9S-22W, GRAHAM COUNTY, KANSAS.

COMMENCED: December 29, 1950

COMPLETED: January 10, 1951

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay	-0-	20	
Clay and Rock	20	40	
Clay	40	70	
Sandy Clay	70	85	
Clay and Shale	85	130	
Shale	130	162	Set 8 5/8" 21# Surface Casing at 162 feet, cemented with 125 sacks of cement.
Shale and Shells	162	1165	
Sandy Shale	1165	1200	
Sand	1200	1470	
Shale and Shells	1470	1775	
Anhydrite	1775	1815	
Shale and Shells	1815	2285	
Lime and Shale	2285	2565	
Lime	2565	2615	
Shale	2615	2640	
Shale and Shells	2640	2975	
Shale and Lime	2975	3220	
Lime	3220	3470	
Lime and Shale	3470	3525	
Lime	3525	3730	
Lime and Shale	3730	3867	
Chert	3867	3880	
Shale	3880	3890	
Arbuckle Lime	3890	3896	
Total Depth		3896	Dry and Abandoned.

CERTIFICATE

I, W. R. Hunter, Vice-President of Barnett Drilling, Inc., hereby certify that to the best of my knowledge and belief the above is a true and correct log of the Vesper Well No. 1, located in the SE<sup>1</sup>/<sub>4</sub> SE<sup>1</sup>/<sub>4</sub> SW<sup>1</sup>/<sub>4</sub> of Section 12-9S-22W, Graham County, Kansas.

W. R. Hunter

Subscribed and sworn to before me, a Notary Public, in and for the County of Sedgwick, State of Kansas, this 15th day of January, 1951.

Delaine Olivier  
Notary Public.

My commission expires May 12, 1951.

**PLUGGING**  
FILE SEC 12-9-22W  
BOOK PAGE 58 LINE 41

1-30-51  
**RECEIVED**  
STATE CORPORATION COMMISSION  
JAN 30 1951  
CONSERVATION DIVISION  
Wichita, Kansas