

State of Kansas



15-665-20712-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 9 1974

CONSERVATION DIVISION  
Wichita, Kansas

10-9-74

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Lowell Moore of C & G Drilling Company has this

date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: C & G Drilling Co., & H. Rosen,

Complete Address: 1107 Union National Building, Wichita, Kansas.

Lease Name: Van Loenen Well No. 1

Location: CN/2-NW-NW Sec. 11 Twp. 9 Rge. (E)(W) 22

County: Graham Total Depth 3640' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Moore was instructed to plug the well as follows:

207'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 650'.

Circulate hole with heavy mud. Pull DP to 875' and displace 110 Cu. Ft.  
cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to  
bottom of cellar.

Very truly yours,

*N. L. Nichols*

Conservation Division Agent