



15-065-20508-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 20 1971
CONSERVATION DIVISION
Wichita, Kansas
12-20-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ronnie Parks of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company,

Complete Address: 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: Willis Well No. 1

Location: App:GNE-SE Sec. 18 Twp. 9 Rge. (E)(W) 22

County: Graham Total Depth 3895' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Parks was instructed to plug the well as follows:

299'--8 5/8" Surface casing, cement circulated with 230 Sx.
Top of Dakota section @ 850'.

Circulate hole with heavy mud. Pull DP to 1075' and displace 110 Cu. Ft. cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. S. Nichols
Conservation Division Agent