

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-163-20199-00-00 Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 22 Twp. 10S Rge. (E) 19 (W)
Location as "NE/CNW/SW" or footage from lines NE NW NE
Lease Owner Thunderbird Drilling, Inc.
Lease Name Winters Well No. 1
Office Address 400 N. Woodlawn, Suite 7, Wichita 67208
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 26, 1969
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced April 26, 1969
Plugging completed April 26, 1969
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Leo Massey of Hays)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3719 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	254'	8-5/8"	4/19/69	-----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud from Total Depth to 600 Feet;
Plug and 70 sax Cement; Mud to
240 Feet, Plug and 20 sax Cement;
Mud to 40 Feet; Plug and 10 sax
Cement. Plugged by Globe Oil Well
Cementing Co. Job completed @
8:00 P.M. on 4/26/69.

RECEIVED
STATE CORPORATION COMMISSION
APR 30 1969
CONSERVATION DIVISION
Wichita, Kansas
04-30-1969

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Globe Oil Well Cementing Co.
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wayne W. Kahmeyer of Sage Drilling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer
500 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of April, 1969
Louise K. Whitted
Louise K. Whitted - Notary Public.

My commission expires November 26, 1970.

15-163-20199-00-00

DRILLERS LOG

WINTERS NO. 1

CASING RECORD: OPERATOR: Thunderbird Drilling, Inc. DESCRIPTION:
8-5/8" @ 254' CONTRACTOR: Sage Drilling Co., Inc. NE NW NE
w/165 sax cement COMMENCED: April 19, 1969 Sec. 22-10S-19W
TOTAL DEPTH: COMPLETED: April 26, 1969 Rooks Co., Kans.
3719' ELEVATION: 2176KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale & Sand	0	40	
Sandy Shale	40	120	
Shale & Clay	120	255	
Shale & Shells	255	985	
Sand	985	1125	
Sand, Red Bed & Shale	1125	1517	
Anhydrite	1517	1555	
Shale & Shells	1555	1965	
Shale w/Lime Streaks	1965	2265	
Lime & Shale	2265	2915	
Shale & Lime	2915	3200	
Lime & Shale	3200	3390	
Lime	3390	3485	
Lime & Shale	3485	3503	
Lime	3503	3599	
Lime & Shale	3599	3719	D&A

RECEIVED
STATE CORPORATION COMMISSION
APR 30 1969
CONSERVATION DIVISION
Wichita, Kansas
04-30-1969

I certify that this is a true and correct copy of the above log to the test of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer
Wayne W. Kahmeyer

Subscribed and sworn to before me this 29th day of April, 1969.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.