


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 24 Twp. 10S Rge. (E) 19 (W) _____
Location as "NE/CNW/SW" or footage from lines _____ NW SW NW

Lease Owner Range Oil Company
Lease Name Vohs Well No. 1
Office Address 402 Insurance Building, Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 22, 19 69
Application for plugging filed _____ 19_____
Application for plugging approved _____ 19_____
Plugging commenced November 22, 19 69
Plugging completed November 22, 19 69
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19_____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Leo Massey of Hays)

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3611 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	230'	8-5/8"	230'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy Mud from Total Depth to 720 Feet,
Plug and 70 Sax Cement; Mud to 210 Feet,
Plug and 20 sax Cement; Mud to 40 Feet,
Plug Bridged w/Kelly; 10 sax Cement to
Base of Cellar; 2 sax Cement in Rat
Hole. Job Completed @ 6 A.M. on 11/22/69.

RECEIVED
STATE CORPORATION COMMISSION
NOV 26 1969
11-26-1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sage Drilling Co., Inc.
Address 500 Bitting Building, Wichita, Kansas 67202


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wayne W. Kahmeyer of Sage Drilling Co. (employee of owner) or (owner or operator) of the above described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer
500 Bitting Building, Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 25th day of November, 19 69

November 26, 1970.
My commission expires _____
Louise K. Whitted - Notary Public.



15-163-20270-00-60

RECEIVED
STATE CORPORATION COMMISSION
NOV 26 1969
CONSERVATION DIVISION
Wichita, Kansas

11-26-1969

DRILLERS LOG

VOHS NO. 1

CASING RECORD:	OPERATOR:	Range Oil Company, Inc.	DESCRIPTION:
8-5/8" @ 230' w/150 sax cement	CONTRACTOR:	Sage Drilling Co., Inc.	NW SW NW Sec. 24-10S-19W Rooks Co., Kansas
TOTAL DEPTH:	COMMENCED:	November 11, 1969	ELEVATION: 2063 KB
3611'	COMPLETED:	November 22, 1969	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay, Rock & Shale	0	160	
Shale & Shells	160	230	
Shale	230	465	
Sand, Shale & Red Bed	465	610	
Shale	610	890	
Sand	890	1095	
Shale & Red Bed	1095	1400	
Shale & Shells	1400	1415	
Anhydrite	1415	1455	
Shale	1455	1780	
Shale & Shells	1780	1850	
Lime & Shale	1850	2515	
Lime	2515	2830	
Lime & Shale	2830	3070	
Lime	3070	3484	
Lime & Chert	3484	3570	
Simpson Dolomite	3570	3611	D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer
Wayne W. Kahmeyer



Subscribed and sworn to before me this 25th day of November, 1969.

Louise K. Whitted
Louise K. Whitted - Notary Public

My commission expires:
November 26, 1970.