

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-163-01978-00-00

API NUMBER 15-1-14-62

LEASE NAME VOUS D#

WELL NUMBER 1

Ft. from S Section Line

Ft. from E Section Line

SEC. 24 TWP. 10 RGE. 19 (E) or (W)

COUNTY ROCK

Date Well Completed 10-12-89

Plugging Commenced 10-12-89

Plugging Completed 10-13-89

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR V.J. HRABE

ADDRESS HAYS KANSAS

PHONE# (913) 628-2056 OPERATORS LICENSE NO. \_\_\_\_\_

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-12-89 (date)

by DENNIS NORMAN / MARVIN MILLER (KCC District Agent's Name)

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? NO

Producing Formation LKC Depth to Top 3110 Bottom 3633 T.D. 3615

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		<u>SURF</u>	<u>174</u>	<u>2 3/8</u>	<u>-</u>	<u>-</u>
		<u>SURF</u>	<u>3615</u>	<u>4 1/2</u>	<u>-</u>	<u>-</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

SEE ATTACH

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ACCIED CEMENTING

Address \_\_\_\_\_

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: V.J. HRABE

STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.

TERRY L. RICHARDSON

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 3406 Summer Lane Hays Ks

SUBSCRIBED AND SWORN TO before me this \_\_\_\_\_ day of \_\_\_\_\_, 19 \_\_\_\_\_

Notary Public

My Commission Expires: \_\_\_\_\_

RECEIVED  
 STATE OF KANSAS  
 LICENSE NO. \_\_\_\_\_  
 NOV 29 1989  
 11-29-1989  
 CORRELATION DIVISION  
 Wichita, Kansas

UOHS D-1

15-163-01978-00-00

10-12-89

RAN TBG & PACKER TO 1400' SET PACKER

Pumped 25 SKS cement mixed w 1 SK HULLS followed  
w/ 25 SKO gel max WP 1000<sup>+</sup> psi ST 100 psi.

Ran wire line in hung up @ 1100 washed dn on  
top of gun w/ WATER got dn to 1390' perforated anydate  
came up the to 860' & perforated DAKOTA

Pumped 250 SKS CEMENT & 900<sup>#</sup> HULLS STILL ON VACUUM  
WAITED ON MORE CEMENT

Pumped 200 SKS cement & 600<sup>#</sup> HULLS STILL ON VACUUM  
<sup>1/2<sup>#</sup> cellulose</sup>  
FLUID LEVEL 90% approx 1300'

SHUT DOWN

10/13/89

RAN wireline to 340'

Pumped 10 SKS cement pressured to 1000 psi broke down to 0 psi.

RAN wire to 860'

Pumped 40 SKS down annulus max 600 psi SHUT IN 250 psi

Pumped 100 SKS down 4 1/2 @ 0 psi

Let set 2 hrs.

Pumped 50 SKS down 4 1/2 @ recommended Opai cement top 350

Pumped 20 SKS gel down 4 1/2 @ 750 psi.

Pumped 40 SKS cement down 4 1/2 w/ 200 LBS HULLS

750 max psi SHUT IN 150 psi.

10/16/89

Checked cement top 100'

RECEIVED  
COMMISSION

NOV 29 1989

CONSERVATION DIVISION  
Wichita, Kansas