



15-103-00358-00-00

WELL LOG - GASAWAY #1

WELL OWNER: The Palmer Oil Corporation  
CONTRACTOR: J. W. Braden Drilling Company  
Commenced: 7/18/51  
Completed: 8/3/51  
RESULTS: Dry Hole

Location: SW SW SE  
Section 24-105-19W  
Rooks County, Kansas  
Elevation: 2018 R. B.

Casing Record

8 5/8" - 223' cemented 175 sacks

Surface	0	60
Sand & shale	60	220
Shale & shells	220	550
Sand & shale	550	1370
Anhydrite	1370	1415
Shale & shells	1415	1705
Shale & lime	1705	2240
Lime	2240	2280
Lime & shale	2280	3190
Lime	3190	3560
Conglomerate	3560	3588 Rotary TD

Formation Tops (R. B.)

Heebner	3174
Lansing	3215
Base K. C.	3454
Cherty Conglomerate	3512
Reworked Arbuckle	3544
Arbuckle	3586

DRILL STEM TEST #1 - 3253 - 3288 Tool open 30 minutes  
Good blow - recovered 90' salt water. BHP 830# Flow Pressure 25#.

DRILL STEM TEST #2 - 3405 - 3452 Tool open 45 minutes  
Fair to poor blow - recovered 4' mud. BHP zero Flow Pressure zero.

This is to certify that the above is a true and correct log, according to the daily drilling reports.

THE PALMER OIL CORPORATION

By A. H. Smith

STATE OF KANSAS )  
COUNTY OF SEDGWICK) SS

08-23-1951

Subscribed and sworn to before me, a Notary Public in said county and state this 22nd day of August, 1951.

Olaf M. Kolling  
Notary Public

My commission expires: 9/30/53.



**PLUGGING**  
FILE SEC 24 T 10 R 19W  
BOOK PAGE 100 LINE 20