


15-163-19365-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Rocks \_\_\_\_\_ County. Sec. 24 Twp. 10 Rge. \_\_\_\_\_ (E) 19 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_ NE Corner  
Lease Owner \_\_\_\_\_ Falcon-Seaboard Drilling Company  
Lease Name \_\_\_\_\_ Vohs \_\_\_\_\_ Well No. 1  
Office Address \_\_\_\_\_ Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_ Dry Hole  
Date well completed \_\_\_\_\_ 12-10-50 \_\_\_\_\_ 19  
Application for plugging filed \_\_\_\_\_ 12-10-50 \_\_\_\_\_ 19  
Application for plugging approved \_\_\_\_\_ 12-10-50 \_\_\_\_\_ 19  
Plugging commenced \_\_\_\_\_ 12-10-50 \_\_\_\_\_ 19  
Plugging completed \_\_\_\_\_ 12-10-50 \_\_\_\_\_ 19  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_ Yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_ Eldon Petty Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ 3730 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				<u>8-5/8</u>	<u>177'</u>	<u>Cemented</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy Mud from bottom of hole to 170' then run a plug and cemented with 15 sacks of cement. Ran another plug at 140' and 10 sacks of cement and filled to ground surface.

(If additional description is necessary, use BACK of this sheet)


Correspondence regarding this well should be addressed to \_\_\_\_\_ Falcon-Seaboard Drlg. Co.  
Address \_\_\_\_\_ Tulsa, Oklahoma

STATE OF KANSAS, COUNTY OF MONTGOMERY, ss.  
FLOYD W. HILD (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. THE VEHICLE SUPPLY & DEVELOPMENT COMPANY

(Signature) \_\_\_\_\_ Floyd W. Hild

P. O. Box 201 \_\_\_\_\_ Gerryvale, Kansas

SUBSCRIBED AND SWORN to before me this \_\_\_\_\_ day of \_\_\_\_\_ December \_\_\_\_\_ 1950



\_\_\_\_\_  
Notary Public.

My commission expires \_\_\_\_\_ July 11, 1952.

28-5091-s 8-50-10M

**PLUGGING**  
FILE SEC 24 T 10 R 19  
BOOK PAGE 48 LINE 31

01-09-1951

15-163-19365-00-00

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for ~~Falcon-Seaboard~~-Veeder Supply & Dev'l. ~~Co.~~ Farm Vohs \_\_\_\_\_ No. #1 Depth 3730'

Contractor Veeder Supply & Development Company Pipe Set 179' of 8-5/8" Csg. Cemented with 120 sx.

Location \_\_\_\_\_ C NE NE NE \_\_\_\_\_ Sec. 24 Twp. 10S Range 19W

Commenced 11-29-50 Completed 12-10-50 County Rooks State Kansas

Surface Soil	0	40	40	Tops:	
Shale Lime	40	177	137	Topeka Lime	- 3084
Shale	177	580	403	Heebner Shale	- 3301
Sand Shale	580	780	200	Dodge Lime	- 3321
Shale Shells	780	985	205	Lansing K.C.	- 3341
Sand	985	1190	205	Conglomerate	- 3573
Sand Shale	1190	1400	210	Arbuckle	- 3695
Shale	1400	1495	95		
Anhydrite	1495	1540	45		
Shale Shells	1540	1850	310		
Shale Shells Salt	1850	1985	135		
Lime Shells Shale	1985	2130	145		
Shale Lime	2130	2830	700		
Shale	2830	2890	60		
Lime Shale	2890	3225	335		
Lime	3225	3575	350		
Conglomerate	3575	3698	123		
Arbuckle Lime	3698	3730	32		
Total Depth	3730'				

AFFIDAVIT

STATE OF KANSAS  
MONTGOMERY COUNTY SS:

FLOYD W. HILD, of lawful age, being duly and solemnly sworn on oath says; I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby know and on oath state, that the above drilling log covering the Vohs #1 Well in Section 24-10S-19W, Rooks County, Kansas, is true and correct.

Further affiant saith not.

THE VEEDER SUPPLY & DEVELOPMENT COMPANY

By: Floyd W. Hild

Subscribed and sworn to before me this 13th day of December, 1950.



Gles Larson  
Notary Public

My Commission Expires: July 11, 1952.

**PLUGGING**  
FILE SEC 24 T 10 R 19W  
BOOK PAGE 48 LINE 31

RECEIVED  
MONTGOMERY COUNTY COMMISSIONER  
JAN X 9 1951  
01-09-1951