


STATE OF KANSAS  
STATE CORPORATION COMMISSION

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Rooks County. Sec. 28 Twp. 10S Rge. (E) 19 (W)  
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SW SW NW  
Lease Owner. Nadel & Gussman  
Lease Name. Miller Well No. 1  
Office Address. P.O. Box 996, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole). Dry Hole  
Date well completed. August 30 19.48  
Application for plugging filed. August 30 19.48  
Application for plugging approved. August 30 19.48  
Plugging commenced. August 30 19.48  
Plugging completed. August 30 19.48  
Reason for abandonment of well or producing formation. Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production. 19.  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well. Merl Rives  
Producing formation. Depth to top. Bottom. Total Depth of Well. 3811 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0'	160'	8 5/8"	160'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


- From 3811' - 160' - Heavy Rotary Mud
- 160' - 158' - Wooden Plug
- 158' - 108' - 20 sacks cement
- 108' - 35' - Heavy Rotary Mud
- 35' - 33' - Wooden Plug
- 33' - 6' - 15 sacks cement
- 6' - Surface - Cellar

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Nadel & Gussman  
Address. P.O. Box 996  
Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.  
Glenn Peel Drilling Co., Inc. (employee of owner) or (owner) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. GLENN PEEL DRILLING COMPANY, INC.



(Signature) BY: *Marion M. Ketchum*  
P.O. Box 359, Hoisington, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of September, 19.48

My commission expires June 4, 1951

22-287 7-47-10M  
PLUGGING  
FILE SEC 28 T 10 R 19W  
BOOK PAGE 53 LINE 25

SEP - 8 1948  
09-08-1948  
Notary Public.

15-163-00100-00-00

DRILLER'S LOG

Company: Nadel & Gussman

Sec. 28 Twp. 10S Rge. 19W  
SW NW NW

Farm: Miller Well No. 1

County: Rooks,  
Kansas

Total Depth: 3811'

Comm: 8-17-48 Comp: 8-30-48

Contractor: Glenn Peel Drilling Co., Inc.

Elevation:

Casing:

Production: Dry

8 5/8" 160' con.

Figures below indicate bottom of formations

Surface Clay	0	50
Sand		160
Shale		445
Sand and Shale		520
Shale and Shells		900
Sand and Shale		1585
Anhydrite		1625
Shale and Shells		1860
Lime and Shale		3415
Lime		3619
Lime and Shale		3753
Conglomerate and Lime		3777
Lime		3811
Total Depth		3811

This is to certify that the above information is, to the best of our knowledge, true and correct.

GLENN PEEL DRILLING CO., INC.

BY: Glenn E. Peel 09-08-1948

SUBSCRIBED AND SWORN to before me this 2nd day of September, 1948

My commission expires June 4, 1951

Marian M. Herfeth  
Notary Public

PLUGGING  
NO. 28 T. 10 S. R. 19 W.  
PAGE 53 LINE 25