

15-163-00292-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Rooks County. Sec. 31 Twp. 10 Rge. 19 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE N $\frac{1}{2}$ E NW

Lease Owner Lohmann-Johnson Drilling Co., In. c

Lease Name Schoenthaler Well No. 1

Office Address 320 Indiana Bank Building, Evansville, Indiana

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed 12/29/50 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 5/26/52 19

Plugging completed 5/26/52 19

Reason for abandonment of well or producing formation Dakota water broke into well.

If a producing well is abandoned, date of last production May 10, 19 52

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top 0 Bottom 3470 Total Depth of Well 3470 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5 1/2		2891'
				8 5/8	210'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with brushed rock to 3470', dumped 4 sacks cement with dump bailer, top of cement 3442'. Mudded hole to 200', set rock bridge, dumped 15 sacks cement, top of cement 155'. Mudded hole to 35', set rock bridge, dumped 10 sacks for cap.

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1952
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Lohmann-Johnson Drilling Co.
Address 320 Indiana Bank Building, Evansville, Indiana

STATE OF Indiana, COUNTY OF Vanderburgh, ss.
James W. Kendall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Kendall
320 Indiana Bank Building, Evansville, Indiana (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of June, 19 52.

My commission expires October 14, 1953 Notary Public.

PLUGGING
JUN 30 1952
PAGE 19 LINK 28

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COPY

COMPANY LOHMANN JOHNSON DRIG. CO., INC. &
GRAHAM-MESSMAN-RINEHART OIL CO.

SEC. 31 T. 10 R. 19W

LOC. NE NE NW

FARM Schonthaler NO. 1

15-163-00292-00-00

COUNTY Rooks

TOTAL DEPTH 3771


COMM. 12-8-50

COMP. 12-28-50

SHOT OR TREATED

CONTRACTOR

ISSUED 3-10-51



CASING

5" 3754'

ELEVATION 2199 R.B.

PRODUCTION 169 bbls / 4% wtr

FIGURES INDICATE BOTTOM OF FORMATIONS.

surface soil	20
sand	50
shale, shells	215
shale	275
shale, sand	1125
sand	1330
shale	1602
anhydrite	1638
shale, shells	2010
lime broken	2362
lime	2470
lime broken	2540
shale, lime	2690
lime broken	2938
shale, lime	3295
lime	3645
conglomerate	3756
conglomerate	3771
Total Depth	

Tops: Corr. to Electric Log.

Heebner	3406
Lansing	3443
Conglomerate	3672
Simpson Sh.	3739
Simpson Sd.	3747
Arbuckle	3759

Shows of Oil:

Lans.	3480-90	oolocastic-fair-good por.spotted stain to saturation
"	3597-3602	sli. oolitic w/fair to poor por, fair spotted stain.
"	3611-19	" " " " " " " "
"	3747-54	clrm-cse sd. clstrs w/dark to dead oil stain
Arb.	3759-62	bf-brn,f.m sln. dol.,fair odor, fair-poor por.,good spotted stain to sat.

RECEIVED
STATE CORPORATION COMMISSION
APR 19 1966
04-19-1966
CONSERVATION DIVISION
Wichita, Kans.