

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-177

API NUMBER 15-163-20,904-00-00

LEASE NAME Keller

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

4950 Ft. from S Section Line

3630 Ft. from E Section Line

LEASE OPERATOR R.P. Nixon Oper. Inc.

SEC. 31 TWP. 10 RGE. 19 (E) or (W)

ADDRESS 207 West 12th Street

COUNTY Rooks

PHONE #(913) 628-3834 OPERATORS LICENSE NO. 5252

Date Well Completed 4-5-79

Character of Well _____

Plugging Commenced 12-28-92

(Oil, Gas, D&A, SWD. Input, Water Supply Well)

Plugging Completed 12-28-92

The plugging proposal was approved on 12-28-93 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 Filed? Yes If not, is well log attached? _____

Producing Formation L/KC, Penn Sand Depth to Top 3505' Bottom 3730' T.D. 3765'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	253'	none
				4 1/2"	3764'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Perf'd 1 hole @ 1610'. Pumped 110sx 65/35 poz, 8% gel, w/3 sx hulls down 4 1/2" casing. Displaced to 1600'. Pumped down 4 1/2" annulus w/50sx 65/35 poz, max pressure 500#. Pumped down 4 1/2" w/250sx 65/35 poz, 8% gel, w/2 hulls. Max pressure 1000#. Plug job complete @ 3:00 pm.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Jay Lan Corp. License No. 5128


Address 207 West 12th St.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Oper. Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Dan Nixon (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 207 West 12th St.



SUBSCRIBED AND SWORN TO before me this 19th day of January

Roxie VonIntel
Notary Public

My Commission Expires: 5-21-93

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1993
CONSULTATION DIVISION
WICHITA, KANSAS
01-02-1993
Form CP-4
Revised 05-88

15-163-20904-00-00

DIGITAL Logging

Radiation Guard Log

COMPANY R. P. NIXON OPERATIONS

WELL NO. 1 KELLER

FIELD MARCOTTE

COUNTY ROOKS STATE KANSAS

Location

NW-NE-NW

Sec. 31 Twp. 10S Rge. 19W

Other Services:

Permanent Datum: GROUND LEVEL Elev. 2203
 Log Measured From K.B., 5 Ft. Above Perm. Datum
 Drilling Measured From KELLY BUSHING

Elev.: K.B. 2208
D.F.
G.L. 2203

Date	4-12-79			
Run No.	ONE			
Depth—Driller	3765			
Depth—Logger	3765			
Btm. Log Inter.	3764			
Top Log Inter.	3100			
Casing—Driller	8-5/8 @ 253	•	•	•
Casing—Logger				
Bit Size	7-7/8			
Type Fluid in Hole	STARCH MUD CL 24,000			
Dena. Visc.	9.2 42			
pH Fluid Loss	6.8 9.6 ml		ml	ml
Source of Sample	FLOWLINE			
R _{na} @ Meas. Temp.	.12 @ 110°F	•	•F	•
R _{mt} @ Meas. Temp.	.085 @ 110°F	•	•F	•
R _{mc} @ Meas. Temp.	.38 @ 110°F	•	•F	•
Source: R _{mt} R _{mc}	CHARTS			
R _{na} @ BHT	.12 @ 110°F	•	•F	•
Time Since Circ.	-			
Max. Rec. Temp.	110 °F		•F	•
Equip. Location	A-1 GB			
Recorded By	W.D. JOHNSON			
Witnessed By	DAN NIXON			

RECEIVED
 STATE COMMISSION
 JUL 16 1992
 CONSERVATION DIVISION
 Wichita, Kansas