


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Rooks County. Sec. 32 Twp. 10S Rge. (E) 19 (W)

Location as "NE/CNW/SW" or footage from lines NE<sup>1</sup>/<sub>4</sub>NE<sup>1</sup>/<sub>4</sub>NE<sup>1</sup>/<sub>4</sub>  
 Lease Owner E. A. Smith  
 Lease Name C. Baldwin Well No. 1  
 Office Address 515 Kennedy Building, Tulsa, Oklahoma  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed 4-28 19 55  
 Application for plugging filed 4-28 19 55  
 Application for plugging approved 4-28 19 55  
 Plugging commenced 4-28 19 55  
 Plugging completed 4-29 19 55  
 Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3775 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	246'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with drilling mud to 240'. Set bottom plug at 240'. Used 15 sacks cement and 1/3 sack hulls. Filled hole to 40' with mud and set top plug at 40'. Used 1/3 sack hulls and 10 sacks cement. Filled to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company  
 Address 607 Union National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
J. Fred Hambright (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. Fred Hambright  
607 Union National Bank Bldg., Wichita, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of May, 19 55

My commission expires August 20, 1956

Arthur P. Deerington  
 Notary Public.  
 STATE CORPORATION COMMISSION

**PLUGGING**  
 FILE SEC 22-10-2-19W  
 BOOK PAGE 115 LINE 37

05-05-1955  
 CONSERVATION DIVISION  
 Wichita, Kansas

WELL LOG

15-163-00847-00-00

COMPANY E. A. Smith

SEC. 32 T. 10S R. 19W

FARM C. Baldwin NO. 1


LOC. NE 1/4 NE 1/4 NE 1/4

TOTAL DEPTH 3775'

COMM. 4-18-55

COMP. 4-29-55

COUNTY Rooks KANSAS



SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED

CASING

20	10
15	EX 8-5/8" 246'
12	6
13	5

ELEVATION 2181 RB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0 - 137	Sand and Shells
137 - 1040	Shale
1040 - 1230	Dakota Sand
1230 - 1590	Red Beds and Shale
1590 - 1615	Anhydrite
1615 - 2100	Shale & Shells
2100 - 2255	Lime
2255 - 2490	Lime and Shale
2490 - 2610	Lime
2610 - 2775	Lime and Shale
2775 - 2905	Broken Lime
2905 - 3305	Lime and Shale
3305 - 3360	Lime
3360 - 3430	Lime and Shale
3430 - 3645	Lime
3645 - 3735	Lime and Shale
3735 - 3755	Conglomerate
3755 - 3775	Arbuckle Lime
3775	T.D.

RECEIVED STATE COURT HOUSE

MAY 1955 05-05-1955 CONSERVATION DIVISION Wichita, Kansas

State of KANSAS } County of SEDGWICK }

SS:

I, J. Fred Hambright of the Lewis Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the C. Baldwin #1 well.

Subscribed and sworn to before me this 3rd day of May 19 55

My Commission Expires: August 20, 1955

PLUGGING

FILE SEC 32 T 10 R 19W BOOK PAGE 115 LINE 37

NOTARY PUBLIC

Handwritten signature of J. Fred Hambright and Notary Public Arthur P. Harrington