

15-163-00081-00-00

BRIDGEPORT OIL COMPANY, INC.,
918 CENTRAL BUILDING,
WICHITA 2, KANSAS.

Well Log-----Atherton "A" #1
NE NE NW 32-10S-19W
Rooks County, Kansas

Elevation-----2185' I&S
Date Started----11-19-44
Date Completed--12-6-44

Casing Record:-
8 5/8" casing cemented @ 203'
with 135 sacks bulk cement.

Rotary Tools---- 0 to 3841'

LOG

0	40	Soil & Clay
40	100	Shale & Sand
100	982	Shale
982	1350	Shale & Sand
1350	1605	Shale, Sand & Pyrite
1605	1820	Shale & Sand Shells
1820	2071	Shale
2071	2181	Shale & Lime Shells
2181	2272	Shale & Lime
2272	2532	Lime
2532	2777	Lime & Shale
2777	2937	Shale & Lime
2937	3005	Shale & Shells
3005	3085	Shale & Lime
3085	3153	Sandy Lime
3153	3205	Shale
3205	3229	Lime
3229	3309	Lime & Shale
3309	3350	Lime
3350	3452	Lime & Shale
3452	3477	Lime & Chert
3477	3503	Shale
3503	3558	Lime & Shale
3558	3603	Lime
3603	3637	Shale & Lime
3637	3694	Lime
3694	3718	Lime & Shale
3718	3771	Conglomerate & Chert
3771	3774	Shale
3774	3807	Conglomerate, Chert & Shale
3807	3815	Conglomerate & Shale
3815	3829	Red Bed & Shale
3829	3841	Arbuckle
3841		T.D.

Plugged and Abandoned 12-6-44

FORMATION TOPS - D.F.

Top Topeka	3191'
Top Heebner	3410'
Top Toronto	3434'
Top Lansing	3456'
Top Conglomerate	3718'
Top Simpson	3802'
Top Arbuckle	3809'

I, Frank Leach, do hereby certify
that the above log is correct to the
best of my knowledge and belief.

BRIDGEPORT OIL COMPANY, INC.

By: Frank Leach

32 10 19W

142 33