

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-163-30926-00-00  
 API NUMBER NA  
 LEASE NAME Palmberg  
 WELL NUMBER 1

RECEIVED  
 KANSAS CORP. COMM.  
 10-31-1997  
 OCT 31 11:39

TYPE OR PRINT  
 NOTICE: Fill out completely and return  
 to Cons. Div. office within 30 days.

LEASE OPERATOR Enterprise Inc.  
 ADDRESS 2708 Barclay  
 CITY, STATE, ZIP Hays, KS. 67601  
 PHONE# 913 625-9699 OPERATORS LICENSE NO. 31240  
 Character of Well Oil  
 Oil, Gas, D&A, SWD, Input, Water Supply Well)

1650 Ft. from S/N Line of Section (circle one)  
2970 Ft. from E/W Line of Section (circle one)  
 SPOT LOCATION SE - NE - SW.  
 SEC. 33 TWP. 10 S. RGE 19 (E or (W)  
 COUNTY Rooks  
 Date Well Completed 4-14-65  
 Date Plugging Commenced 8-29-97  
 Date Plugging Completed 8-29-97

The plugging proposal was approved on 8-29-97 (date)  
 by Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? NO If not, is well log attached? NO

Producing Formation(s) LKC Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3574

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
				<u>8 5/8</u>	<u>172</u>	<u>0</u>
				<u>4 1/2</u>	<u>3574</u>	<u>0</u>

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Tubing to 1426'. Pump 50 5x5 cement w/hulls. Tbg. to 1000'. Pumped 20 5x5 cement. Tubing to 500' & circulated cement to surface with 50 5x5. Pulled Tbg. Tied out. Production casing and pumped 40 5x5 cement. Max 500# SIP 300#.  
Tied onto Annulus and pumped 50 5x5 cement. Max 500# SIP 300#.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Randy's Well Service

License No. 31287  
 Address P.O. Box 393 Plainville KS. 67663

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Steve Weilert

STATE OF Kansas COUNTY OF Ellis, ss.

Steve D Weilert (Employee of Operator or (Operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Steve D Weilert

(Address) 2708 Barclay Hays KS 67601

SUBSCRIBED AND SWORN TO before me this 29<sup>th</sup> day of October, 19 97

Linda K. Carreira  
 Notary Public

My Commission Expires: 7-20-01

 LINDA K. CARREIRA  
 NOTARY PUBLIC  
 STATE OF KANSAS Form CP-4  
 My Appt. Exp. 2-20-01 Revised 12-92