


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks County. Sec. 33 Twp. 10S Rge. 19W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SE SW
Lease Owner Martin & Keller
Lease Name Keller Well No. 1
Office Address 1035 Kennedy Bldg., Tulsa, Okla. 74103
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-19-65 19
Application for plugging filed 9-19-65 19
Application for plugging approved 9-19-65 19
Plugging commenced 9-19-65 19
Plugging completed 9-19-65 19
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Moreland, Ks.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3595 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	181'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug @ 550' with 20 sacks cement
Plug @ 170' with 20 sacks cement
Plug @ 35' bridged with 1/2 sk. hulls & 10 sks. cement to cellar bottom

RECEIVED
STATE CORPORATION COMMISSION
SEP 27 1965
09-27-1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address P. O. Box 486, Great Bend, Kansas 67530


STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of September, 19 65

My commission expires April 1, 1967



Wanda Nichols
Notary Public.

15-163-30130-00-00

DRILLER'S LOG

COMPANY: Martin & Keller
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: KELLER #1
 LOCATION: NE SE SW Sec. 33-10S-19W
 ROOKS COUNTY, KANSAS
 COMMENCED: 9-12-65
 COMPLETED: 9-19-65

0	500	Surface shale
500	950	Shale, redbed
950	1050	Sand, redbed
1050	1105	Shale
1105	1280	Shale, sand
1280	1488	Redbed
1488	1524	Anhydrite
1524	1610	Shale
1610	2356	Shale & Shells
2356	3439	Lime, shale
3439	3302	Lime
3302	3380	Lime with Shale
3380	3595	Lime
	<u>3595</u>	<u>RTD - D. & A.</u>

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 27 1965
 09-27-1965
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" used surface casing @ 181' with 145 sacks 60-40 Posmix Sunset

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Keller #1 well, located NE SE SW of Section 33, Township 10 South, Range 19 West, Rooks County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 23rd day of September, 1965.



Ulanda Nichols

Ulanda Nichols

My Commission Expires:
 April 1, 1967