

KANSAS

M
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

FEB 17 1972
CONSERVATION DIVISION
Wichita, Kansas

15065-20527-00-00

02-17-1972

Operator's Full Name Don E. Pratt,

Complete Address Drawer #370, Hays, Kansas.

Lease Name Elmer Dreiling Well No. A-1

Location APP C N/2 N/2 NW
1320' EWL & 140' SNL of NW/4 Sec. 32 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4092'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 11:00 PM Day 15 Month 2 Year 1972

The above well was plugged as follows:

238'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 110 Cu. Ft. cement
thru DP from 1275' to 950'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *H. G. Daniels*
Well Plugging Supervisor

DATE 2-17-72
INV. NO. 5187-W